BRUHAT BANGALORE MAHANAGARA PALIKE
RAJARAJESHWARI NAGARA ZONE

SL No

Name of the Work:-Construction and laying of new pipeline works and cistern (MWS) for existing and new borewells in ward no 16

Sl. No.	Description of work	Unit	No.	Length (m)	Breadth (m)	Depth (m)	Quantity	Rate/Unit (Rs.)	Amount (Rs.)
1	KSRB 2-2.2 : Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1(b) / 2.3.5(Page.no.5,Item no.2.4)								
	Pipiline								
	nandhini lay out		1	400.00	0.60	0.90	216.00		
			1	480.00	0.60	0.90	259.20		
			1	300.00	0.60	0.90	162.00		
			1	400.00	0.60	0.90	216.00		
			1	360.00	0.60	0.90	194.40		
			1	250.00	0.60	0.90	135.00		
		cum					1182.60	288.36	341015.00
	Basic Rate=		267.00						
	Add A.W.8%=		21.36						
	Total=		288.36						
	KSRB13-9.1 : Providing and fixing to wall, ceiling and floor high density polyethylene pipes 6.00 kgf/sq.cm working pressure 63mm outside diameter with special flange, compression type fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications. Specification No.KBS 13.2.15.2 / 13.9(Page.no.94,Item no.13.73.2)								
	nandhini lay out		1	400.00			400.00		
			1	480.00			480.00		
			1	300.00			300.00		
			1	400.00			400.00		
			1	360.00			360.00		
			1	250.00			250.00		
		RMT					2190.00	373.68	818359.00
	Basic Rate=		346.00						
	Add A.W.8%=		27.68						
	Total=		373.68						
	KSRB 2-4 : Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5 m. including cost of all labour complete as per specifications.(Page.no.6,Item no.2.11)								
	Basic Rate=		72.00						

Scanned by CamScanner